



## **Addendum No. 5**

### **Coyote Valley Open Space Preserve Public Access Improvement Project**

**RFB-2026-03**

April 6, 2026

The following revisions are hereby incorporated into project documents. Revisions are described below and attached herein. All other conditions remain the same.

Each bidder shall be responsible for acknowledging, on the Bid Form, that they have received all issued Addenda.

#### Clarifying Questions and Answers

- a. *What is the weight limit for bridge on site that will need to be crossed to complete the pathway work?*

**Answer: Maximum allowable vehicular load is 10,000 lbs. (equipment + load).** The clear width of bridge deck is 5'-6" by 60'.

If contractor proposes using the bridge for construction access, a protective layer of at least 3/4" plywood must be placed on the deck to prevent damage. The Santa Clara Valley Open Space Authority shall review and approve proposed creek crossing means and methods and BMPs.